



**REQUEST FOR PROPOSAL #2026-08**

**SUPPLY AND INSTALLATION OF PLAY STRUCTURE  
SUMMERSTOWN ESTATES PARK**

**ADDENDUM 1 of 1**

**NOTE: Addenda are to be acknowledged in proposal submissions.**

---

**June 5, 2026**

**Question 1**

The specification references a drainage line within the site preparation scope. Could you please confirm if drainage pipe/Big O pipe is required as part of the playground site preparation?

**Answer 1**

A perforated, sock-wrapped drainage pipe (Big "O" pipe) shall be installed as part of the drainage system where required to achieve proper drainage of the playground and underlying materials.

As specified in the RFP, a drainage line shall be installed and rundown slope to a point permitting natural drainage. Minimum grade fall shall be ¼ inch per foot. There are existing ditches located approximately 20-40 metres south and west of the proposed playground area.

Final layout, extent, and configuration of the drainage system shall be determined by the Contractor to meet the specified grading and drainage performance requirements.

---

**Question 2**

If OPipe is required, could you please advise the approximate length, location, and intended discharge point? Please also confirm if the intent is for a new French drain system or connection to an existing drainage/storm system is available.

**Answer 2**

Refer to Answer 1 above. The Contractor shall be responsible for determining the required length, layout, and configuration of the drainage system necessary to achieve compliance with the RFP requirements, including proper drainage to a suitable natural outlet.

---

**Question 3**

Could you please confirm if excavated material/tailings may remain on site for town to remove?

**Answer 3**

Excavated material is not to remain on site.

---

**Question 4**

Would it be possible to receive an extension to allow time for a site visit prior to submission?

**Answer 4**

The closing date for the RFP remains as originally published.

---

**Question 5**

Please confirm if the proposed playground footprint/play area sizing may be determined by the successful proponent based on selected equipment layout and CSA requirements, and that there is no existing pit currently on site.

**Answer 5**

Correct, please refer to page 24, sections 5 and 6 of the RFP.

**Question 6**

The budget of \$60,000 does not allow for all the requested items including the swing. Is there a priority list if not all items can fit into the budget?

**Answer 6**

Proponents are required to include all specified items identified in the RFP within the stipulated project budget. Submissions that do not meet all requirements will be evaluated accordingly.

---

**End of Addendum 1 of 1.**