



Township of South Glengarry
 6 Oak Street, P.O. Box 220, Lancaster, ON, K0C 1N0
 T: (613) 347-1166 | F: (613) 347-3411
www.southglengarry.com

2026-04 - Sutherland Creek Bridge Rehabilitation Forum of Submission

Company Name:			
Address:			
HST No:			
Name & Position:			
Email:		Phone:	
Signature:		Date:	

Item	Description	OPS/ SP	Units	Qty	Unit Price	Total
PART A - GENERAL						
1	Sitework including Mobilization, Demobilization	SP1	LS	1		
2	Traffic Management	706, SP2	LS	1		
3	Environmental Protection / Erosion and Sediment Control	182, 805, SP3	LS	1		
4 (P)	Field Office for Contract Administrator (Provisional)	SP4	wk	12		
PART B – ROADWAY & GRADING						
5	Removal of Asphalt Pavement - Full Depth	510	m2	19		
6	Cutting Existing Pavement	510	m	38		
7	Pavement Marking, Permanent	710, SP12	LS	1		
8	Hot Mix Asphalt HL-3	310, SP11	LS	1		
9	Site Restoration - Topsoil, Hydraulic Seed and Mulch	802	LS	1		

Item	Description	OPS/ SP	Units	Qty	Unit Price	Total
PART C - STRUCTURAL						
10	Access to Work Area, Work Platform and Scaffolding	928, SP5	LS	1		
11	Concrete Removal - Partial Depth - Type A	928, SP5	m ³	0.5		
12	Concrete Removal - Partial Depth - Type B	928, SP5	m ³	0.8		
13	Concrete Removal - Partial Depth - Type C	928, SP5	m ³	1.1		
14	Abrasive Blast Cleaning of Reinforcing Steel	929	m ²	34		
15	Reinforcing Steel Bar	905	t	0.4		
16	Dowels into Concrete	904, SP6	ea.	116		
17	Grout Pads	904, SP10	LS	1		
18	Fabrication of Structural Steel	906, SP7	LS	1		
19	Delivery of Structural Steel	906, SP7	LS	1		
20	Erection of Structural Steel	906, SP7	LS	1		
21	Coating Existing and New Structural Steel	911, SP7	LS	1		
22	Environmental Protection During Coating of Existing Structural Steel	911	LS	1		
23	Bridge Deck Waterproofing	914	m ²	19		
24	Joint Sealing Compounds, Joint Seals & Joint Fillers	920	LS	1		
25	Bridge Jacking for Bearing Replacement	922	LS	1		
26	Bearings	922	ea	12		
27	Concrete Patches, Unformed Surface	906, SP7	m ³	0.5		
28	Concrete Patches, Formed Surface	906, SP7	m ³	1.9		

Item	Description	OPS/ SP	Units	Qty	Unit Price	Total
PART D – SDG Wood Creek Bridge Rehab						
29	Site Work - Wood Creek Bridge	SP14	LS	1		
30	Traffic Management - Wood Creek Bridge	706, SP15	LS	1		
31	Dowels into Concrete - Wood Creek Bridge	905	ea.	98		
32	Stainless Steel Bar - Wood Creek Bridge	905	t	0.2		
33	Preformed Seals, Joint Fillers, Joint Seals, Joint Sealing Compounds, and Waterstops (Compression Seal) - Wood Creek Bridge	920, SP16	LS	1		
34	Concrete Removal - Partial Depth - Type A- Wood Creek Bridge	928, SP18	m ³	0.8		
35	Abrasive Blast Cleaning of Exposed Reinforcing Steel - Wood Creek Bridge	929, SP17	m ²	8		
36	Two-component polyurethane Patch Material - Wood Creek Bridge	SP19	ea.	46		
Total Parts A-C					\$	
Total PARTD					\$	

SUB TOTAL

\$

HST

\$

TOTAL

\$

TO: **THE CORPORATION OF THE
TOWNSHIP OF SOUTH GLENGARRY
6 Oak Street
Lancaster, Ontario K0C 1N0
Clerk@Southglengarry.com**

I/We, having carefully examined any and all sites of the proposed work and all documents relating thereto, do hereby submit and offer in accordance therewith to enter into an Agreement as and when required by the Township of South Glengarry, in strict accordance with the said documents and such further details as may be supplied and to supply all necessary labour, material, and plant to complete the work in the time specified and agree to be bound by the terms and conditions of this procurement process.

DATED AT _____ THIS _____ DAY OF _____ 2026

Signature of Witness

Signature of Respondent

** Please Ensure to submit bid deposit is submitted to Township prior to submitting this form. Bid deposits delayed by Banking institutions and/or not received by the date and time specified at tender closing shall be deemed non-compliant **